

Richie Beyer

From: jharvill [jharvill@chamberscounty.com]
Sent: Monday, September 13, 2010 9:58 AM
To: Patrick D McDougald; Richie Beyer
Attachments: Statewide County Bridge Assessment #2.xls; _Certification_.txt

Couple of notes:

Either data was incomplete or absent for Cleburne, Greene, Hale, Lawrence, Lee, Lowndes, Marshall, Montgomery, Tuscaloosa, and Wilcox Counties. I used the data given to us from Renee Flowers to complete the spread sheet for those counties. Let me know if we need any additional info. The data that was assumed was:

- Culverts 35%, 50 foot width, \$70 per sq. ft.
- Pre-Cast 45%, 28 foot width, \$90 per sq. ft.
- AASHTO 20%, 28 foot width, \$110 per sq. ft.
- Lengths for all structures were increased 125% from existing.
- Approach work for all structures was assumed to be 60% of the structure cost.

Josh Harvill
Chambers County Assistant Engineer
PO Box 650
LaFayette, Al 36862
Office: (334) 864-4361