PROPOSAL NO. INQUIRY 2027-PW3

October 30, 2026

FOR THE CONSTRUCTION OF:
ANNUAL PAVING

AUTAUGA COUNTY, ALABAMA

Proposal of
Contractor Name: _____

Of (City, State): _____

ALDOT Contractor Identification Number: _____
(To be used to document E-Verify)

Alabama General Contractors License Number: _____

For the Construction of: Annual Paving

The specifications are hereto attached.

In order to be considered, proposals must be received at the location and time below:

Autauga County Commission
John Mark Davis, County Engineer
135 N. Court St., Suite B
Prattville, Alabama 36067
Phone: (334) 361-3761

BEFORE: 10:00 AM (CST) ON WEDNESDAY, NOVEMBER 18, 2026
Bids will be opened as soon thereafter as practicable.
Award will be made at the next regularly scheduled meeting of the Autauga County Commission.

NOTICE TO CONTRACTORS

Gentlemen:

Autauga County is taking bids for labor, equipment, materials, and any incidentals required to complete the work of the following items required for the Inquiry 2027-PW3 Annual Paving of the County. This bid is intended to comply with the Rebuild Alabama Act, No. 2019-2, and Alabama Code Title 39, the Alabama Public Works Law. Bidders shall be required to comply with the provisions of the Rebuild Alabama Act, No. 2019-2 and Title 39 of the Alabama Code regardless if the requirement is explicitly detailed in the bid proposal or not. This bid shall be in effect from January 1, 2027, until December 31, 2027 covering any Proceed Orders issued by Autauga County during that time frame. This project will be eligible for a Certificate of Exemption as provided by Act 2021-372.

Sealed bids will be received by the Autauga County Commission until **10:00 AM (CST) on Wednesday, November 18, 2026,** and then publicly opened as soon thereafter as practicable. Award will be made at the next regularly scheduled meeting of the Autauga County Commission. Only bids from contractors or material suppliers listed on the Alabama Department of Transportation (ALDOT) approved list of contractors and material suppliers will be accepted. All bids must be marked with the word "BID" on the outside of the bid package along with Bid Proposal for Inquiry 2026-PW3, the bid date and the Alabama General Contractor's License Number.

The contractor shall meet all Alabama Department of Transportation (ALDOT) Bonding and Licensing requirements as well as all applicable laws, ordinances, and codes of the U. S. Government, the State of Alabama, any relevant municipality, and Autauga County, and, specifically and without limitation, shall comply with all provisions of the Beason-Hammon Alabama Taxpayer and Citizen Protection Act, commonly referred to as the Immigration Act.

All bid items shall be placed in accordance with the bid items and specifications, current revision of the Alabama Department of Transportation Standard Specifications (non-metric edition), and any Supplemental Specifications approved by the Autauga County Engineer. This project is being advertised, let to contract, and administered by an awarding authority other than the Alabama Department of Transportation (ALDOT). All references made in the standard specifications and in other related and included documents of this proposal, to ALDOT (except as applies to references made to ALDOT considering a bidder to be disqualified from bidding, or to the awarding authority consulting or interacting with ALDOT, etc.), the "State", the "Department" or "Public Works Department", etc. shall be understood to mean the awarding authority for this project.

Should the bidder desire to offer a substitute for any item listed in this proposal, a full description of the item(s) offered as substitutes shall be submitted to the County Engineer at least 48 hours before the time stated for opening the bids. The County Engineer will issue an addendum, if necessary, to all bidders who have obtained a bid proposal. Each bidder shall include a copy of the addendum with his/her signature indicating they had received the addendum when submitting their bid. If no addendum is issued, the substitute will not be considered in determining the lowest responsible bidder. No bid proposals or additional addenda will be issued 24 hours prior to the time of the bid opening.

Signature on bid must be in ink. Bids made out in pencil will NOT be accepted. Autauga County reserves the right to accept or reject all Bids or any portion thereof. Autauga County Commission's Hours of Operation are 8:00 A.M. to 4:30 P.M. (CST)) from Monday through Friday. Please remit all Bids and Inquiries to John Mark Davis, Autauga County Engineer, 135 N Court St. Suite B, Prattville, Alabama 36067.

BID PROPOSAL FOR

INQUIRY 2027-PW3
ANNUAL PAVING

To the Autauga County Commission:

The undersigned shall give Autauga County at least 48 hours' notice in advance of performing work at any site once a Purchase Order has been issued by Autauga County. The undersigned must receive written permission to work on Saturdays, Sundays, or County recognized holidays 48 hours prior to such work commencing. Unless otherwise directed in writing by the County Engineer, the undersigned will be expected to begin work within 15 calendar days after issuance of the Purchase Order.

Each Proceed Order shall designate the amount of working days or calendar days allowed. Should the undersigned fail to complete the project or projects specified in the Proceed Order within the working days or calendar days stipulated, liquidated damages shall be assessed as defined in section 108.10 in the current revision of the Alabama Department of Transportation Standard Specifications or as amended by Special Provision.

A certified check, drawn on an Alabama Bank, or bid bond, for $10,000 made payable to the Autauga County Commission is enclosed as evidence of good faith. Within 15 days upon notification of bid award, the undersigned shall submit a Performance Bond for, $1,500,000.00 and a Payment Bond for $750,000.00 to Autauga County Commission along with the contract documents, certificate of public liability insurance, certificate of proof of workman's compensation insurance, and business license. The undersigned shall provide to the County his/her Alabama Department of Transportation (ALDOT) Vendor Identification Number as shown on the E-Verify Compliance Status List on the ALDOT website as proof of enrollment in E-Verify.

The undersigned shall submit the Advertisement of Project Completion to Autauga County immediately following the completion and acceptance of all work required for this contract. The County Engineer will submit the advertisement to the Association of County Commissions of Alabama (ACCA) to be posted on a website maintained by ACCA for a period of four consecutive weeks.

Upon completion and acceptance of all work required, the undersigned will be paid upon presentation of the following:

a. A properly executed and duly certified voucher for final payment.
b. A release of all claims and claims of liens against the awarding authority arising by virtue of the contract.

c. Proof of Advertisement of project completion (AL Code 39-1-1(f) requires a 30-day waiting period after the notice has run before final settlement can be made)

The undersigned agrees: **Final payment will be made within 35 days after all the above requirements are met; Partial Payments, to be paid no more than monthly, for each Proceed Order will be provided under this contract; Retainage shall be withheld on each Proceed Order as required under Code of Alabama Section 39-2-12.**

By submitting this proposal, the contracting parties affirm, for the duration of the agreement, that they will not violate the federal immigration law or knowingly employ, hire for employment, or continue to employ an unauthorized alien within the State of Alabama. Furthermore, a contracting party found to be in violation of this provision shall be deemed in breach of the agreement and shall be responsible for all damages resulting therefrom.

INSURANCE REQUIREMENTS

The Contractor, at its sole expense, shall obtain and maintain in full force the following insurance to protect the Contractor and the Autauga County Commission, Alabama at limits and coverages specified below. These limits and coverages specified are the minimum to be maintained and are not intended to represent the correct insurance needed to fully and adequately protect the Contractor.

All insurance will be provided by insurers licensed to conduct business in the State of Alabama and shall have a minimum A.M. Best rating of A- VII and must be acceptable to the Autauga County Commission. Self-insured plans and/or group funds not having an A.M. Best rating must be submitted to the Autauga County Commission for prior approval.

No work shall be performed until proof of compliance with the insurance requirements has been received by the Autauga County Commission.

(a) Worker's Compensation and Employers Liability

Part One: Statutory Benefits as required by the State of Alabama

Part Two: Employers Liability

Each Accident	$3,000,000
Each Employee	$3,000,000
Policy Limit	$3,000,000

i. U. S. Longshoremen & Harborworkers' Act (USL&H) - Required if contract involves work near a navigable waterway that may be subject to the USL&H law.

ii. Maritime Endorsement (Jones Act) - Endorsement required if contract involves the use of a Vessel. Or include coverage for "Master or Members or Crew" under "Protection and Indemnity" coverage

Bodily Injury by accident (Each Accident)	$3,000,000
Bodily Injury by disease (Aggregate)	$3,000,000

(b) Commercial General Liability

Coverage on an Occurrence form with a combined single limit (Bodily Injury and Property Damage combined) as follows:

	Projects
Each Occurrence	$3,000,000
Personal and Advertising Injury	$3,000,000
Products/completed Operation Aggregate	$3,000,000
General Aggregate	$3,000,000

- Coverage to include:
  - Premises and operations
  - Personal Injury and Advertising Injury
  - Independent Contractors
  - Blanket Contractual Liability
  - Explosion, Collapse and Underground hazards
  - Broad Form Property Damage
  - Products/Completed Operations - This shall remain in effect for 24 months beyond completion and acceptance by owner of the project, whichever is later.
  - Railroad Protective Liability Insurance if work involves construction, demolition or maintenance operations on or within 50 feet of a railroad.

The contractor shall name the Autauga County Commission, its officers, appointees, employees, and agents as additional insured for claims arising out of the Contractors and/or Subcontractors work. The ISO Form CG 20 10 11 85 or a comparable form that is no more restrictive shall be required. The Additional Insured form MUST include the current Operations and Products/Completed Operations of the contractor. The naming of the additional insured does not obligate the additional insured to pay any premiums due.

Aggregate limits to be on a "per project" basis OR an Owners and Contractors Protective Liability Policy shall be provided in the name of Autauga County Commission, the contractor and Subcontractors. Limits to be the same as above Commercial General Liability.

(c) Automobile Liability

Covering all Owned, Non-Owned, and Hired vehicles with a Combined single limit (bodily injury and property damage combined) of $3,000,000 each accident. The policy shall name Autauga County Commission its officers, appointees, employees, and agents as an Additional Insured.

(d) Protection and Indemnity Insurance

If the contract involves work aboard an Owned, Non-Owned or Hired Vessel, Liability coverage in the amount of $3,000,000 per occurrence shall be maintained.

(d) Indemnification and Liability

Under this section the term County shall include Autauga County, the Autauga County Commission, the officers, appointees, department heads, agents, and employees of the Autauga County Commission.

The County shall not be liable for any injury to the person or property of any person, firm, or corporation resulting directly or indirectly from Contractor's performance of this Contract, and the Contractor assumes full and complete responsibility therefore.

The Contractor shall further indemnify the County and hold the County safe and harmless from any and all liability, lawsuits, judgments, attorney fees, and other costs incurred by the County in defending any claim or lawsuit made against the County by any person, firm, or corporation arising directly or indirectly out of any work performed by the Contractor pursuant hereto or any breach or alleged breach of duty or responsibility of the Contractor related thereto.

Waiver of Subrogation

The Workers Compensation Policy shall contain a Waiver of Subrogation in favor of the Autauga County Commission, its officers, appointees, employees, and agents.

Certificate of Insurance

A Certificate of Insurance evidencing the above minimum requirements must be provided to and accepted by the Autauga County Commission PRIOR to commencement of any work on the contract. Each policy shall be endorsed by the issuing insurer to provide thirty (30) days prior written notice of cancellation to the Autauga County Commission.

SPECIFICATIONS FOR INQUIRY 2027-PW3
ANNUAL ASPHALT PAVING

The unit prices below will apply to each Proceed order issued and should be based on County Wide Pricing. A Proceed Order may include multiple projects or sites. Each Proceed Order shall note the items required and estimated quantities per project or site.

A Job Mix Design must be submitted, by the Contractor, to Autauga County following the receipt of a Proceed order. PRICE ADJUSTMENTS will be made to all Asphalt Materials in accordance with the following: It is understood and agreed that the price per ton of materials bid is based on prices at the time of opening bids. Prices on contracts developed from this bid will be adjusted based on the PRICE INDEX per gallon of asphalt as determined by the **ALDOT Asphalt index for the month of November 2026.** Any increase or decrease in asphalt prices will be determined and adjusted by the price index for the month in which delivery and placement is made. Adjustment will be made in accordance with the current ALDOT Specifications. This adjustment shall apply to the amount of liquid used in the plant mix material only.

No reclaimed asphalt shingles (RAS) will be allowed in any plant mix item. Recycled Asphalt Mix (RAP) shall be limited to a maximum of 20% in any bituminous plant mix wearing surface layer items and shall be limited to a maximum of 25% in all other bituminous plant mix items. Upon request, Test Reports shall be submitted on all materials before Payment will be made. The Contractor shall furnish flagmen and portable traffic control devices (or other method approved by the County Engineer) in accordance with current revision of the Manual of Uniform Traffic Control Devices (MUTCD). Traffic control and standard advisory project sign placement (as directed by the Engineer) is being bid as part of this bid inquiry and shall be the responsibility of the contractor to install and maintain all signs during construction. The County reserves the right to review the contractor's traffic control plan and require work to cease if the plan is not adequately handling traffic. The contractor is responsible for traffic control and any issues that arise due to the contractor's ability to handle traffic during construction. All temporary traffic striping shall take place at the end of each day's production of asphalt leveling/wearing surface or surface treatment placement in accordance with the current version of the Alabama Department of Transportation Standard Drawings and Standard Specifications. The Autauga County Engineer shall serve as the final authority for all phases of workmanship and materials.

All materials to be placed shall be in accordance with the current revision of the Alabama Department of Transportation Standard Specifications and/or approved by the Autauga County Engineer. All materials shall meet ALDOT specifications and/or be approved by the Autauga County Engineer. (Note: The following items and subsequent bid prices shall in no way affect any project let on contract by Autauga County). All items shall be bid for any location in Autauga County. All material shall be in compliance with
sections 212, 401, 405, 408, 410, 424, 650, 652, 656, 701, and 740 of the ALDOT Specifications.

1. "PATCHING"
Price per ton, including tack coat, to remove in place pavement and/or base, and place 1" MAS hot plant mix at areas where pavement has been removed. Work consists of areas where pipes have been replaced, bridge approaches repaired, patching, etc. Price to include all materials, labor, and equipment required to roll and smooth existing base (as directed by the Engineer), clean roadway, haul, spread, and compact the asphalt material in place in compliance with the applicable section of the ALDOT specifications. Rates to vary from 200 lbs./square yard to 600 lbs./ square yard. On a single proceed order this item may be used in conjunction with items 1 thru 16.

$_____/Ton	25-150 Tons
$_____/Ton	151-300 Tons
$_____/Ton	301-600 Tons
$_____/Ton	601-1200 Tons
$_____/Ton	1201 Tons and Above

2. "WIDENING"
Price per ton, including tack coat, to place 1" MAS hot plant mix to widen an existing roadway surface. Price to include all materials, labor, and equipment required to notch out edge of pavement, clean roadway, tack the edges (as directed by the Engineer), haul, spread (with a road widener), provide proper shape (as directed by the Engineer), and compact the asphalt material in place. Price to also include machine grading and flushing shoulder with windrowed material from notching out of the shoulder (as directed by the Engineer) in compliance with the applicable sections of the ALDOT specifications. The shoulder material notched out of for the placement of the widening may not exceed the actual amount of asphalt widening placed in a day's work. Placement ranges may range from 1' to 3' in width. Rates for widening may range from 200 lbs./square yard to 600 lbs./square yard. On a single proceed order this item would only be used in conjunction with items 1 thru 16. (i.e. Autauga County would not issue a proceed order for this item without one or more of the other items listed).

$_____/Ton	50-250 Tons
$_____/Ton	251-750 Tons
$_____/Ton	751-1500 Tons
$_____/Ton	1501-2,500 Tons
$_____/Ton	2,501 Tons and Above

3. "MILL AND FILL"
Price per ton, including tack coat, to mill an existing asphalt surface 0.75" to 1.5" in depth, and resurface with ½" MAS hot plant mix. This shall cover uniform and non-uniform layers. Price to include all labor, equipment, and materials required to mill to the required depth, clean roadway of millings, and haul millings off-site to appropriate location. Price also to include application of tack coat as well as haul, spread, and compact the asphalt material in place in compliance with applicable ALDOT specifications. Uniform rates may range from 80 lbs./square yard to 165 lbs./square yard. On any given proceed order, Autauga County shall keep up to a maximum of 10 fully loaded tri-axle truckloads of asphalt millings from milling operations, and the contractor shall haul millings to the Autauga County Engineer's Office at 511 West 4th Street, Prattville, AL 36067. County forces (labor and equipment) shall stockpile millings hauled to Engineer's Office. On a single proceed order this item may be used in conjunction with items 1 thru 16.

$_____/Ton	50-250 Tons
$_____/Ton	250-500 Tons
$_____/Ton	501-1000 Tons
$_____/Ton	1001-2,000 Tons
$_____/Ton	2,000-4,000 Tons
$_____/Ton	4,000 Tons and Above

4. "E TREATMENT WITH POLYMER ON EXISTING ROAD"
Price per square yard complete in place (SYCIP) to place 401B-100 Bituminous Treatment E (with Polymer Additive) on an existing roadway surface. Price to include all materials, labor, and equipment to clean roadway, apply treatment, and compact material in place in compliance with the applicable section of the ALDOT specifications. Work shall be in accordance with Section 401 of the ALDOT specifications. On a single proceed order this item may be used in conjunction with items 1 thru 16.

With Limestone Aggregate

$_____/SYCIP	1,000 -5,000 SY
$_____/SYCIP	5,001 -10,000 SY
$_____/SYCIP	10,001-20,000 SY
$_____/SYCIP	20,001-40,000 SY
$_____/SYCIP	40,001-80,000 SY
$_____/SYCIP	80,001-120,00 SY
$_____/SYCIP	120,001 SY and Above

5. "G TREATMENT WITH POLYMER ON EXISTING ROAD"
Price per square yard complete in place (SYCIP) to place 401B-108 Bituminous Treatment G (with Polymer Additive) on an existing roadway surface. Price to include all materials, labor, and equipment to clean roadway, apply treatment, and compact material in place in compliance with the applicable section of the ALDOT specifications. Work shall be in accordance with Section 401 of the ALDOT specifications. On a single proceed order this item may be used in conjunction with items 1 thru 16.

With Limestone Aggregate

$_____/SYCIP	1,000 -10,000 SY
$_____/SYCIP	10,001 -20,000 SY
$_____/SYCIP	20,001-40,000 SY
$_____/SYCIP	40,001-80,000 SY
$_____/SYCIP	80,001-120,000 SY
$_____/SYCIP	120,001-240,00 SY
$_____/SYCIP	240,001 SY and Above

6. "LEVELING & WEARING SURFACE"
Price per ton, including tack coat, to place ½" MAS hot plant mix on an existing roadway surface, a widened roadway (item 2), or a surface treatment. This shall cover uniform layers, non-uniform leveling layers, and/or spot leveling. Price to include all materials, labor, and equipment required to clip edge of pavement, clean roadway, haul, spread, and compact the asphalt material in place in compliance with the applicable section of the ALDOT specifications. Rates may range from 100 lbs./square yard to 200 lbs./square yard. Spot leveling shall be as directed by the County Engineer. On a single proceed order this item may be used in conjunction with items 1 thru 16.

$_____/Ton	100-500 Tons
$_____/Ton	501-1000 Tons
$_____/Ton	1001-2,000 Tons
$_____/Ton	2,001-4,000 Tons
$_____/Ton	4,001-8,000 tons
$_____/Ton	8,001 Tons and Above

7. "AGGREGATE SHOULDERS"

Price per ton to install 430B-043 Aggregate Surfacing (1" Down, Crusher Run). Price to include all labor, equipment and materials required to clean the roadway, haul, spread (with a road widener), shape to provide proper slope (as directed by the Engineer) and compact the crushed aggregate material in place in compliance with applicable ALDOT specifications. Placement ranges may range from 1' to 3' in width to flush and establish a sound road shoulder. Final placement and approval of the finished shoulder shall be at the discretion of the County Engineer. On a single proceed order this item would only be used in conjunction with items 1 thru 16. (i.e. Autauga County would not issue a proceed order for this item without one or more of the other items listed).

$_____/Ton	25-100 Tons
$_____/Ton	101-251 Tons
$_____/Ton	251-500 Tons
$_____/Ton	501-1000 Tons
$_____/Ton	1001-2,000 Tons
$_____/Ton	2,001 Tons and Above

8. "TOPSOIL"

Price per cubic yard (loose truck bed measurement) to install 650A-000 TOPSOIL. Price to include all labor, equipment and materials required to clean the roadway, haul, spread (with a road widener), shape to provide proper slope (as directed by the Engineer) and compact the material in place in compliance with applicable ALDOT specifications. Placement ranges may range from 1' to 3' in width to flush and establish a sound road shoulder. Final placement and approval of the finished shoulder shall be at the discretion of the County Engineer. On a single proceed order this item would only be used in conjunction with items 1 thru 16. (i.e. Autauga County would not issue a proceed order for this item without one or more of the other items listed).

$_____/Ton	20-100 cyd
$_____/Ton	101-200 cyd
$_____/Ton	201-400 cyd
$_____/Ton	401-600 cyd
$_____/Ton	601-1,000 cyd
$_____/Ton	1,001 cyd and above

9. "MACHINE GRADING SHOULDERS"
Price per station for 212A-000 MACHINE GRADING SHOULDERS. Price to include all labor and equipment required to pull, shape, and grade shoulders to provide proper slope (as directed by the Engineer) and prepare shoulder material as required to prepare for final grass establishment and/or the placement of additional shoulder material (i.e. item 8 "TOPSOIL"). Final placement and approval of the finished shoulder shall be at the discretion of the County Engineer. On a single proceed order this item would only be used in conjunction with items 1 thru 16. (i.e. Autauga County would not issue a proceed order for this item without one or more of the other items listed).

$_____/Station

10. "SEEDING AND MULCHING"
Price per acre for 652A-100 SEEDING and 656A-010 MULCHING. Price to include all labor, equipment, and materials required to prepare existing and/or new shoulder for grass establishment. Cost to include seed and mulch meeting applicable ALDOT specifications. Final grass establishment and approval of the work shall be at the discretion of the County Engineer. On a single proceed order this item would only be used in conjunction with items 1 thru 16. (i.e. Autauga County would not issue a proceed order for this item without one or more of the other items listed).

$_____/acre (652A-100 SEEDING)
$_____/acre (656A-010 MULCHING)

11. "PRIME"
Price per square yard complete in place (SYCIP) to place 401A-000 Bituminous Treatment A on a prepared roadway base surface. Price to include all materials, labor, and equipment to clean, prime, and sand roadway in compliance with the applicable section of the ALDOT specifications. Work shall be in accordance with Section 401 of the ALDOT specifications. On a single proceed order this item would only be used in conjunction with items 1 thru 16. (i.e. Autauga County would not issue a proceed order for this item without one or more of the other items listed).

$_____/SYCIP	1,000-5,000 SY
$_____/SYCIP	5,001-10,000 SY
$_____/SYCIP	10,001-20,000 SY
$_____/SYCIP	20,001-40,000 SY
$_____/SYCIP	40,001 SY and Above

12. "KG TREATMENT WITH POLYMER ON PRIMED SURFACE"

Price per square yard complete in place (SYCIP) to place 401B-107 Bituminous Treatment KG (with polymer additive) on a primed roadway base surface. Price to include all materials, labor, and equipment to clean primed surface, apply treatment, and compact material in place in compliance with the applicable section of the ALDOT specifications. Work shall be in accordance with Section 401 of the ALDOT specifications. On a single proceed order this item would only be used in conjunction with items 1 thru 16. (i.e. Autauga County would not issue a proceed order for this item without one or more of the other items listed).

$_____/SYCIP	1,000-5,000 SY
$_____/SYCIP	5,001-10,000 SY
$_____/SYCIP	10,001-20,000 SY
$_____/SYCIP	20,001-40,000 SY
$_____/SYCIP	40,001 SY and Above

13. "BINDER ON NEW AND/OR RECONSTRUCTED ROAD"

Price per ton, including tack coat, to place 1" MAS hot plant mix on a base surface, primed surface, or a bituminous surface treatment. Price to include all materials, labor, and equipment required to roll and smooth existing base, clean roadway, haul, spread, and compact the asphalt material in place in compliance with the applicable section of the ALDOT specifications. Work consists of areas where bridge approaches repaired, new road ways, reconstructed roadways, reclaimed roadways, etc. Rates may range from 225 lbs./square yard to 350 lbs./square yard. On a single proceed order this item may be used in conjunction with items 1 thru 16.

$_____/Ton	100-500 Tons
$_____/Ton	501-1000 Tons
$_____/Ton	1001-2,000 Tons
$_____/Ton	2,001-4,000 Tons
$_____/Ton	4,001-8,000 tons
$_____/Ton	8,001 Tons and Above

14. 701C-000 BROKEN TEMPORARY TRAFFIC STRIPE
On a single proceed order this item would only be used in conjunction with items 1 thru 16 (i.e. Autauga County would not issue a proceed order for this item without one or more of the other items listed).

$_____/Mile

15. 701C-001 SOLID TEMPORARY TRAFFCIC STRIPE
On a single proceed order this item would only be used in conjunction with items 1 thru 16(i.e. Autauga County would not issue a proceed order for this item without one or more of the other items listed).

$_____/Mile

16. 740B-000 CONSTRUCTION SIGNS
On a single proceed order this item would only be used in conjunction with items 1 thru 16(i.e. Autauga County would not issue a proceed order for this item without one or more of the other items listed).

$_____/SQFT

Note: "MAS" = Maximum Aggregate Size

The undersigned hereby states that this Bid Proposal is to the best of their knowledge; their true and correct bid, except for changes initiated herein, and is submitting these bid items for review and consideration.

Signature of Bidder (If Firm or Individual) _____

By: _____

Address of Bidder _____

Name and Address of Member of Firm _____

_____

Email address of Company Contact _____

Phone Number _____

****

Signature of Bidder (Corporation) _____

_____ **Business Address** _____

President

_____ **Business Address** _____

Secretary/Treasurer

Attest: _____ **Incorporated in** _____

(State)

(Corporate Seal)

BIDS WILL NOT BE CONSIDERED UNLESS THIS FORM AND FORM FOR BID BOND IS USED AND IS SIGNED IN INK BY PRINCIPAL AND SURETY.

BID BOND

KNOW ALL MEN BY THESE PRESENTS:

That _____ of
(Name of Contractor)

_____
(Address)

as Principal, and _____ of
(Name of Surety)

_____, as Surety,
(Address)

are held firmly bound unto AUTAUGA COUNTY COMMISSION, a Political Subdivision of and Body Corporate in the State of Alabama as Obligee, in the full and just sum of **Ten Thousand Dollars ($10,000)** lawful money of the United States, for the payment of which sum, well and truly to be made, we bind ourselves, our heirs, executors, administrators, successors and assigns, jointly and severally, firmly by these presents.

WHEREAS, the said Principal is herewith submitting its proposal for

INQUIRY 2027-PW3
ANNUAL PAVING

The condition of this obligation is such that if the aforesaid Principal shall be awarded the contract the said Principal will, within the time required, enter into a formal contract and give a good and sufficient bond to secure the performance of the terms of and conditions of the Contract, then this obligation to be void; otherwise, the Principal and the Surety will pay unto the Obligee the difference in money between the amount of the Contract as awarded and the amount of the proposal of the next lowest responsible bidder, which amount shall not exceed $10,000. If no other bids are received, the full amount of the proposal guarantee shall be so retained or recovered as liquidated damages for such default.

Witness our hands and seals this _____ day of _____, 20_____.

Signature of Individual Bidder: (Use only where bidder is an individual)

_____, Doing business as _____
(Name of Individual) (Business Name)
Business Mailing Address: _____

Name of Corporation, Partnership, or Joint Venture:

_____

(Name of Partnership, Joint Venture or Corporation)

Business Mailing Address: _____ BY: _____ (L.S.)

(Signature and Position or Title of Officer Authorized to Sign Bids and Contracts for Firm)

_____

(Address)

Business Mailing Address: _____ BY: _____ (L.S.)

(Signature and Position or Title of Officer Authorized to Sign Bids and Contracts for Firm)

_____

(Address)

Business Mailing Address: _____ BY: _____ (L.S.)

(Signature and Position or Title of Officer Authorized to Sign Bids and Contracts for Firm)

_____

(Address)

(Corporate Seal)
Attest:

_____

(Secretary)

Name of State under the laws of which the Corporation was chartered:

_____

(State)

(Corporate Seal)
Attest:

_____

(Secretary)

Name of State under the laws of which the Corporation was chartered:

_____

(State)

SURETY: _____

(Name of Surety)

BY (AGENT): _____

(Attorney in Fact)

AGENT'S ADDRESS: _____

_____

(Mailing Address)

NOTICE: Valid Power of Attorney Must Be Attached.

END OF PROPOSAL